



**PETROVIETNAM OIL CORPORATION
JOINT STOCK COMPANY**

PROJECT


**EXPANSION OF 40,000M³ STORAGE CAPACITY
AT PETEC HAI PHONG**

PACKAGE

ENGINEERING, PROCUREMENT, CONSTRUCTION AND INSTALLATION

**TECHNICAL REQUISITION DOCUMENT FOR

DIESEL GENERATOR**

						
A	30/09/2025	Issued for Bid	NXH	PQP	PQP	VLT
Rev.	Date	Purpose	Prepared	Checked	Reviewed	Approved



EPC CONTRACTOR



PTSC THANH HÓA - ĐẠI DŨNG III - PHƯƠNG ANH
CONSORTIUM

Document No:

TRD-004

	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

REVISION RECORD SHEET

No	Content of Revision	Rev	Date
1	Issued for Bidding	A	30/09/2025







	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

TABLE OF CONTENTS

1. INTRODUCTION.....	4
1.1. PROJECT BACKGROUND.....	ERROR! BOOKMARK NOT DEFINED.
1.2. PURPOSE	4
1.3. DEFINITIONS AND ABBREVIATIONS	4
2. SCOPE OF SUPPLY AND WORK	ERROR! BOOKMARK NOT DEFINED.
2.1. SCOPE OF SUPPLY	5
2.2. SCOPE OF WORK.....	6
3. TECHNICAL REQUIREMENTS.....	7
3.1. GENERAL.....	8
3.2. DESIGN LIFE, AVAILABILITY AND RELIABILITY..	ERROR! BOOKMARK NOT DEFINED.
3.3. PROTECTIVE COATING AND PAINTING	ERROR! BOOKMARK NOT DEFINED.
3.4. PREPARATION FOR SHIPMENT.....	ERROR! BOOKMARK NOT DEFINED.
3.5. DELIVERY TIME	9
3.6. GUARANTEE AND WARRANTY	ERROR! BOOKMARK NOT DEFINED.
3.7. SPARE PARTS	10
3.8. CONFLICTING REQUIREMENTS	10
3.9. DEVIATION LIST	10
4. INSPECTION AND TESTS.....	10
5. VENDOR DOCUMENT REQUIREMENT	10
6. TÀI LIỆU ĐÍNH KÈM.....	ERROR! BOOKMARK NOT DEFINED.

	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	  
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

1. INTRODUCTION

Project name: Expansion of 40,000m³ Storage Capacity at PETEC Hai Phong Petroleum Terminal Project

Client: PETEC HAI PHONG

Contractors: PTSC THANH HÓA – ĐẠI DŨNG III– PHƯƠNG ANH

The total expanded capacity is 40,000m³ as follows:

- 01 tank 10,000m³ tank (with float): containing RON95 – T33
- 03 tanks of 10,000m³: containing DO - T34, T35, T36
- 01 tanks of 1500m³ containing fire water and auxiliary items....

2. GENERAL INFORMATION



2.1. Purpose of Document

This document is to specify minimum requirements for Emergency Diesel Generator Sets which shall be used for O Mon GDC, An Minh LFS and Mui Tram LFS of Block B - O Mon Gas Pipeline Project.

The document identifies applicable technical documentation relevant to the design, manufacturing, construction, inspection and testing and delivery of the Emergency Diesel Generator Set and shall be read in conjunction with the applicable project.

2.2. Definitions and Abbreviations

OWNER	NAM DINH VU UNIONCHEM TERMINAL
CONTRACTOR	The EPC company or consortium which is awarded the EPC contract
PURCHASER	The party which places the purchase order or signs the contract
SUPPLIER/ BIDDER	The company on which the purchase order or contact for supply of the goods or services is placed
Purchase Order	The order issued by the PURCHASER consisting of the Purchase Order including Terms and Conditions and attachments thereto including but no limited to Datasheets and Drawings, Specifications including referenced documentation therein and all other documents and attachments

	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

3. LANGUAGE AND UNITS

3.1. Language

All documents and drawings to be submitted shall be lettered in English language.

3.2. Units of Measurement

Units of measurement for all engineering documents shall be in the System International (SI).



4. ITEMS AND QUANTITIES

No.	Item no	Q'ty	Description	Remark
1	Diesel Generator	1	3P, 455 kVA	
2	Synchronization switchboard panel	1	3P/1500A,	

5. SCOPE OF WORK

The **VENDOR**'s scope of work for each skid shall include but not limited to:

- Electrical, Instrumentation and Mechanical, Process design of all equipment and materials
- Mechanical/ Electrical and performance guarantee for the package and supplied items
- Inspection and Testing
- Provision of material certification, test certificates, etc.
- Surface preparation, painting, protective coating
- Design of foundation bolting
- First fill of lubricants, chemicals and consumables & for Load test
- Load test from No load from overload and reports
- FAT and FAT reports
- Site support for installation, startup commissioning, SAT and SAT reports
- List of recommended two years operating spares (quote as optional)
- Special tools for operation, installation and maintenance purposes, where required (quote as optional)
- List of start-up and commissioning spare parts including consumables (quote as optional)
- Long term preservation and packing for transportation where required



	<p align="center">EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG</p>	
<p align="center">TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR</p>		<p>Tài liệu số: TRD-004</p>
		<p>Phiên bản số: A</p>

- Drawings and documentation as specified in Supplier Data Requirements Form included in the TRD
- VENDOR shall assist EPC Contractor to provide all package design/manufacture information for obtaining Authority Approvals for the installation and operation.
- Complete Bill of Materials of Emergency Diesel Generator Set and all associated equipment
- Technical assistance and training for operating personnel if specified in datasheet or functional requirements.

6. SCOPE OF SUPPLY

The TRD covers the minimum technical requirements for the design, engineering, fabrication, construction, inspection and testing, documentation, supply and delivery of Emergency Diesel Generator Set consisting of, but not limited, to the following:

- Diesel Engine
- Generator / Alternator
- Engine starting systems
- Coupling and non-sparking coupling guard
- Local control panel including AVR
- All necessary instrumentation with engine gauge panel
- Diesel fuel system (including all On-skid piping facilities)
- Diesel fuel day tank (Sized for 8 hours operation as minimum) complete with flame arrestor and other accessories, including level gauge, fill connection, drain and vent connections, auto fill control valve
- Lube oil system
- Jacket Water Cooler (Radiator)
- Air Inlet Filters
- On-Skid cabling and internal wiring between all equipment and components
- On-Skid cable trays of galvanized steel
- On-Skid inter-connecting piping for the package piped to the skid edge terminated with a flange
- Combustion air and exhaust system
- Expansion Joints, Elbows
- Electronic Governor
- Generator output circuit breaker
- Generator terminal box
- Digital serial interface to the PCS for measured value, status and alarm display
- Hardwire interface to the SDS for tripping

	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

- Hardwire interface to the Main Switchgear & MCC for ATS control
- Utility equipment/devices to facilitate operation/maintenance of generator set
- Structural steel skid
- Interior lighting
- Unit enclosure
- Stainless steel nameplates
- Packing seal assembly
- Accessories (Earthing bosses M10 sizes, anchor bolts & nuts, lifting lugs, ...).

7. OUT OF SCOPE

- Power Supply cables from Generator terminal to Main Switchgear & MCC
- Communication cables / control cables from Generator to Control room
- Exterior lighting (Lighting for outside of Generator Set Enclosure)
- Earthing cable for skid to earthing loop
- Off skid piping to Diesel Storage Tank



8. CONFLICTING REQUIREMENTS

VENDOR shall notify PURCHASER of any conflicts between this TRD, specifications, the related data sheets, the Codes and Standards and any other specifications noted herein. Resolutions and/or interpretation precedence shall be obtained from PURCHASER in writing before proceeding with the design/manufacture.

9. DEVIATION LIST

VENDOR's quotation shall be in full conformity with PURCHASER's requirements. Unless exceptions, deviations or alternatives are clearly defined and listed on the attached PURCHASER's form "Deviation List" as provided in Appendix No. 2 and submitted with VENDOR's quotation, the requirements and conditions of this Requisition shall be deemed to be accepted by the VENDOR.

It will be assumed that all PURCHASER's requirements are followed without exception if VENDOR did not provide any deviation in writing. Any deficiencies in this respect that are identified during or subsequent to contract execution shall be rectified at VENDOR's cost.

	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

10. GENERAL REQUIREMENTS

10.1. General

The Emergency Diesel Generator Set shall be strictly in accordance with data sheets, drawings, specifications, codes, and standards specified.

Compliance by the **VENDOR** with the provision of this specification does not relieve him of his responsibility to furnish the package/ material and accessories of a proper design to meet the specified duty and / or local codes governing health and safety.

All applicable documents mentioned below are attached to the request for inquiry. However, if the **VENDOR** is not in possession of any of the listed or referenced **PURCHASER** documents, it shall be **VENDOR**'s sole responsibility to obtain them from the **PURCHASER**. Otherwise, it shall be assumed that the **VENDOR** has received, read and understood the total contents of the documents.

All materials and parts shall be new, unused and free from defects and imperfections that would adversely affect the life or performance of the system.

No fabrication would commence until **PURCHASER** has approved the Manufacturing procedure specifications, data sheets.

PURCHASER's approval on project documents does not relieve **VENDOR** of compliance with applicable codes, specifications, safety design, or meeting the requirements of governmental agencies.

Any work and documentation related to facilitating design appraisal approvals and inspection from **PURCHASER** appointed Certification Authority (CA) and QA/QC Inspector (TPI) shall also be included in **VENDOR** 's scope of supply.



10.2. Design Life, Availability and Reliability

The design life of the facility and all associated equipment, components and systems is **minimum 20 years**.

All components which for practical, safety or cost-efficiency reasons are unable to meet the required design life shall be identified as soon as possible. Their expected service life shall be informed to **PURCHASER** and provision made in the system design for maintenance to extend component life or routine change-out.

10.3. Preparation for Shipment

VENDOR is requested to submit the procedure for load-out, handling, transportation and preservation in the technical proposal.

	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

Equipment shall be prepared for export shipment and shall be created to provide maximum protection during shipment and extended outdoor storage.

Any equipment liable to be damaged during shipment shall be disassembled, packed separately, shipped with the unit and reassembled onsite under the supervision of Vendor 's commissioning/start-up technician.

Each crate shall be clearly identified in accordance with the customer's specification. As a minimum the crate shall be marked with the Purchase Order number, the item number, the shipping mass and the delivery address.

Flanged process connections shall be protected by steel cover plates bolted in place with at least 4 bolts then sealed with tape. All nozzles and branches shall be protected against damage during transportation and erection.

The equipment shall be suitably preserved to maintain in good condition throughout the phases of storage until ready to be operated.

Threaded nozzle connections shall be protected with threaded plugs. However, telltale holes in reinforcing pads shall be protected with non-hardening plastic sealant or packed with grease.

Exposed machined surfaces, including threads extending beyond the nuts, shall be protected with an easily removable rust-preventive coating.

All equipment shall be suitably protected for shipment and securely anchored during transit. Separate or loose parts shall be completely boxed with identification tag.

Tools and spare parts shall be packed in metal boxes suitable for long term storage. The boxes shall be galvanized or coated in accordance with Project requirement.

10.4. Delivery time



The SUPPLIER/ BIDDER shall deliver the goods to PURCHASE's or OWNER's warehouse accordance with the project schedule.

For more details, please refer to [Attachment #5 Project Schedule](#).

10.5. Guarantee and Warranty

The VENDOR shall have final and total responsibility for the design and performance of all material supplied under this requisition.

The VENDOR shall replace and install without cost to the PURCHASER any materials, supplies which fails due to defects in material or workmanship if the defect is observed and/or such failure occurs within the guarantee/warranty period. Acceptance of this order will signify acceptance of all conditions of this guarantee.

	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

The guarantee period starting from delivery of the Goods and ending after the first twenty-four (24) months of in-service use of the Goods (such period not to exceed 36 (thirty-six) months from the date of delivery of the Goods to Buyer).

10.6. SPARE PARTS

The SUPPLIER/ BIDDER shall include, as part of his bid, a detailed, list of recommended spare parts for commission, initial startup and two years continuous operation.

These spares shall be costed for separate purchase.

10.7. CONFLICTING REQUIREMENTS

SUPPLIER/ BIDDER shall notify PURCHASER of any conflicts between this TRD, specifications, the related data sheets, the Codes and Standards and any other specifications noted herein. Resolutions and/or interpretation precedence shall be obtained from PURCHASER in writing before proceeding with the design/manufacture.

10.8. DEVIATION LIST

SUPPLIER/ BIDDER's quotation shall be in full conformity with PURCHASER's requirements. Unless exceptions, deviations or alternatives are clearly defined and listed on the attached "**Att #3.2 Technical Bid Forms**" in the **Attachment #3 – Technical Bid Proposal.**" and submitted with SUPPLIER/ BIDDER's quotation, the requirements and conditions of this Requisition shall be deemed to be accepted by the SUPPLIER/ BIDDER.

11. INSPECTION AND TESTS

Inspection and tests shall be made by the SUPPLIER/ BIDDER in accordance with:

Test & Inspection should be carried out acc. to the applicable codes, specification and standards.

Maker's standard plan & procedure as approved by PURCHASER



Local regulation, if any

The OWNER and/or PURCHASER inspector shall hold a right to be present at any manufacturing stage of the equipment and/or materials.

Refer to **Attachment #4 Vendor Data Documents List** for the detailed.

12. VENDOR DOCUMENT REQUIREMENT

The BIDDER shall complete all required technical information in the forms provided under "**Attachment #3 – Technical Bid Proposal.**"



	EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG	
TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR		Tài liệu số: TRD-004
		Phiên bản số: A

In particular, the form entitled “**Attachment #3.1 – Technical Bid Requirement Forms**” is mandatory. Failure by the SUPPLIER/BIDDER to complete this form shall render the bid invalid.

The Contractor shall be providing the forms, documents, and drawings as listed in “**Attachment #4 – Vendor Data Documents List.**”

13. ATTACHMENT DOCUMENT

STT	Đính kèm	Tên tài liệu	Ghi chú
1.	Attachment #1	Scope of Supply	
2.	Attachment #2	Technical Support Document	
3.	Attachment #3	Technical Bid Proposal	
4.	Attachment #4	Vendor Data Documents List	
5.	Attachment #5	ITP Typical Inspection and Test Plan	
6.	Attachment #6	Project Schedule	

	<p align="center">EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG</p>	
<p align="center">TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR</p>		<p>Tài liệu số: TRD-004</p>
		<p>Phiên bản số: A</p>

ATTACHMENT #1

SCOPE OF SUPPLY



SCOPE OF SUPPLY - PURCHASER



Project:



TRD no.

Date: 10/2/2025

Rev: 1

SCOPE OF SUPPLY - PURCHASER

No	Tag#	Description	Unit	QTY	Remark
1	MP-02	Diesel generator 455 kVA, 380V, 3 Phase, 4 wire, 50 Hz, min IP31	set	1	
2		Synchronization switchboard panel, 3P/1500A, IP42	set	1	

	<p align="center">EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG</p>	
<p align="center">TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR</p>		<p>Tài liệu số: TRD-004</p>
		<p>Phiên bản số: A</p>

ATTACHMENT #2

TECHNICAL SUPPORT DOCUMENT

- *Att #2.1 Datasheets*
- *Att #2.2 Drawings*



TỔNG CÔNG TY THƯƠNG MẠI VÀ KỸ THUẬT ĐẦU TƯ - CTCP


DỰ ÁN

MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG

GÓI THẦU

TƯ VẤN LẬP BÁO CÁO NGHIÊN CỨU KHẢ THI

**BẢNG THÔNG SỐ KỸ THUẬT CHO
MÁY PHÁT ĐIỆN DIESEL
(DATASHEET FOR DIESEL GENERATOR)**

2	05/10/2023	Xuất bản để phê duyệt	NNP	LTT	LTT	NQT	
1	29/09/2023	Xuất bản để xem xét	NNP	LTT	LTT	NQT	
LXB.	Ngày	Mô tả	Thực hiện	Kiểm tra	Phê duyệt	CECO	PETEC
	CÔNG TY CỔ PHẦN THIẾT KẾ CÔNG NGHIỆP HÓA CHẤT					Số tài liệu: PTHP-EL-DAS-001	
						Tổng trang : 12 (bao gồm trang bìa)	



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 3 of 12

DATASHEET FOR DIESEL GENERATOR

MECHANICAL GENERAL DATA SHEET

1		
2		
3		Sheet No.
4	General	3, 4
5	Internal combustion engine - diesel	5, 6, 7, 8
6	A.C synchronous generator data	9, 10, 11
7	Low pressure and atmospheric tank data sheet	12
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		
29		
30		
31		
32		
33		
34		
35		
36		
37		
38		
39		
40		
41		
42		
43		
44		
45		
46		
47		
48		
49		
50		
51		
52		
53		
54		
55		
56		
57		
58		
59		
60		
61		
62		



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 4 of 12

DATASHEET FOR DIESEL GENERATOR

MECHANICAL GENERAL DATA SHEET	
1	
2	GENERAL
3	1 This data sheet document covers diesel engine generator package for PETEC Hai Phong Petroleum Storage
4	
5	2 Vendor shall complete main parts of the data sheet included with difference quotation. Where necessary, vendor shall copy blank data
6	sheets for any difference rated items between the two types of package
7	
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	
21	
22	
23	
24	
25	
26	
27	
28	
29	
30	
31	
32	
33	
34	
35	
36	
37	
38	
39	
40	
41	
42	
43	
44	
45	
46	
47	
48	
49	
50	
51	
52	
53	
54	
55	
56	
57	
58	
59	
60	
61	
62	



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 5 of 12

DATASHEET FOR DIESEL GENERATOR

INTERNAL COMBUSTION ENGINE DATA SHEET												
1												
2	Applicable	<input checked="" type="checkbox"/>	Proposal	<input type="checkbox"/>	Purchase	<input type="checkbox"/>	As built					
3	For				Unit	Direct driven Generator						
4	Site	PETEC Hai Phong			Service	Power generator						
5	Driven equipment	AC Generator			No. required	One						
6	Note:	<input checked="" type="checkbox"/>	Indicates Information to be completed by Purchaser			<input checked="" type="checkbox"/>	By Manufacturer					
7	DRIVEN MACHINE											
8	Driven machine	AC Generator			Starting torque	(*)	kg.m					
9	Duty	Continuous			GD2 value	(*)	kg.m ²					
10	Power Required at shaft (normal)	(*)	kVA		RPM	1500						
11	Power Required at shaft (Max.)	(*)	kW		RPM	(*)						
12	Rotation of machine view from coupling and	<input checked="" type="checkbox"/>	CW		<input type="checkbox"/>	CCW						
13	Method of drive	<input checked="" type="checkbox"/>	Flexible / Rigid coupling		<input type="checkbox"/>	V-Belts		<input type="checkbox"/>	Gear drive - right angle			
14	Drive through power take off clutch	(*)										
15	Recommended rated power of prime mover at site	(*)										
16	SITE DATA				UTILITIES							
17	Location				Steam	(*)	kg/hr	(*)	barg	(*)	°C	
18	<input checked="" type="checkbox"/>	Indoor	<input type="checkbox"/>	Heated	<input type="checkbox"/>	Under roof	Water	(*)	m ³ /hr	(*)	barg	
19	<input type="checkbox"/>	Outdoor	<input type="checkbox"/>	Unheated	<input type="checkbox"/>	Partial sides	Electric	220/380	Volts	50	Hz	
20	<input type="checkbox"/>	Grade	<input type="checkbox"/>	Mezzanine	<input type="checkbox"/>	Other	Starting air	(*)	Nm ³ /start	(*)	Min. barg	
21	<input type="checkbox"/>	Electric area classification	<input checked="" type="checkbox"/>	Non Hazardous		Inst. Air	(*)	Nm ³ /hr	(*)	barg		
22		Zone	N/A	Group	N/A	Temp. class	N/A	Service	(*)	Nm ³ /hr	(*)	Min. barg
23	<input type="checkbox"/>	Winterization Required	<input checked="" type="checkbox"/>	Tropicalization Required								
24	Site data				FUEL SYSTEM							
25	<input checked="" type="checkbox"/>	Altitude	< 1000	m	<input checked="" type="checkbox"/>	Barometer	1.01	barA	<input checked="" type="checkbox"/>	Fuel grade	Diesel	
26	<input checked="" type="checkbox"/>	Range ambient temperature	Min. 5.4	°C	Max. 42.0	°C	<input checked="" type="checkbox"/>	Treatment required	(*)	Supplied by	(*)	
27	<input checked="" type="checkbox"/>	Relative humidity	Max. 95%		<input checked="" type="checkbox"/>	Fuel pressure required	Max. (*)	Min. (*)	Barg			
28	Unusual conditions				<input checked="" type="checkbox"/>	Fuel data	(*)	MJ/kg	SG (*)	@	(*)	
29	<input type="checkbox"/>	Dust	<input type="checkbox"/>	Fumes	<input checked="" type="checkbox"/>	Others	Humidity (corrosive)	Contaminants (*)				
30	MANUFACTURER'S SPECIFICATION											
31	CONSTRUCTION & PERFORMANCE FEATURES											
32	Manufacturer	(*)			Engine Model	(*)						
33	Cylinder arrangement	(*)			No. of Cylinders	(*)						
34	Bore / Stroke	(*)			Compression ration	(*)						
35	Speed	(*)			RPM	Mean piston speed	(*)					
36	Charging	<input type="checkbox"/>	Normally Aspirated	<input type="checkbox"/>	Mech. Supercharged	<input checked="" type="checkbox"/>	Turbo charged	<input type="checkbox"/>	Intercooled			
37	Rating	(*)			<input checked="" type="checkbox"/>	With	<input type="checkbox"/>	Without	10% Overload provision			
38	Performance Standard	BS 5514 / ISO 3064			BMEP at rated load,	(*)						
39	Type combustion chamber	(*)			Firing order	(*)						
40	Rotation view from coupling end	(*)			Type of cold Starting aid	(*)						
41	Engine cooling	<input checked="" type="checkbox"/>	Air cooled		<input checked="" type="checkbox"/>	Water cooler						
42	Method of stopping	<input checked="" type="checkbox"/>	Manual		<input checked="" type="checkbox"/>	Automatic						
43	Method of starting	<input checked="" type="checkbox"/>	Manual		<input checked="" type="checkbox"/>	Automatic						
44	Rated engine power at standard operating condition	(*)			kW	(To suit generator requirements)						
45	(With engine driving all its ancillaries bur excluding radiator fans & motor driven pumps)											
46	Power required for driving	(*)	Motor driven fans	(*)	Motor driven pumps	(*)						
47	Rated engine power under site condition (Guaranteed, no negative tolerance)	(*)										
48	Specific fuel consumption (Guaranteed), at Vendor's work	(*)			(kg/kW-hr)							
49	<input checked="" type="checkbox"/>	10% Overload	(*)	<input checked="" type="checkbox"/>	Full load	(*)	<input checked="" type="checkbox"/>	3/4 load	(*)	<input type="checkbox"/>	1/2 load	(*)
50	Engine Governing	(*)			Speed range	(*)	RPM	NEMA class	(*)			
51	Governor type	Electronic			Make / Model	(*)						
52	Governor control mechanism	(*)			<input checked="" type="checkbox"/>	Manual		<input type="checkbox"/>	Remote			
53												
54	Note:											
55	(*)	Vendor to advise										
56												
57												
58												
59												
60												
61												



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 6 of 12

DATASHEET FOR DIESEL GENERATOR

1	<input type="checkbox"/>	Hand starting with starting handle									
2	<input checked="" type="checkbox"/>	Battery starting with cable lugs and									
3	<input checked="" type="checkbox"/>	Batteries No.	(*)	Make	(*)	Rating	(*)				
4	<input checked="" type="checkbox"/>	Starter	(*)	Make	(*)	Rating	(*)				
5	<input checked="" type="checkbox"/>	Dynamo	(*)	Make	(*)	Rating	(*)				
6	<input checked="" type="checkbox"/>	Regulator & cut-off	(*)	Make	(*)	Rating	(*)				
7	<input type="checkbox"/>	Compressed air starting with interconnecting piping & valves etc.									
8	<input type="checkbox"/>	Air motor	Make	(*)	Model	(*)	Air supplies purchaser	(*)	Pressure	(*)	
9	<input type="checkbox"/>	Air compressor type	(*)	Make / Model	(*)	Capacitor	(*)				
10		Pressure	(*)	Barg	Driven by	(*)	Rating/speed	(*)			
11		Start-stop switch for compressor			(*)	<input type="checkbox"/>	Manual	<input type="checkbox"/>	Automatic		
12	<input type="checkbox"/>	Air receiver with pressure gauge relief valve & manual drain valve (*)									
13	<input type="checkbox"/>	Air receiver capacity					(*)	<input checked="" type="checkbox"/>	Design code		
14	<input type="checkbox"/>	Hydraulic starting with charge accumulator and auto charging system									
15	<input type="checkbox"/>	Hydraulic motor	(*)	Make	(*)	Model	(*)	<input type="checkbox"/>	Glow plug start	<input type="checkbox"/>	Other
16											
17	WATER COOLING SYSTEM										
18	<input checked="" type="checkbox"/>	Radiator cooling including interconnecting piping &									
19	<input checked="" type="checkbox"/>	Radiator with temperature	<input type="checkbox"/>	Control valve	<input checked="" type="checkbox"/>	Expansion / make up water tank	(*)				
20	<input checked="" type="checkbox"/>	Fan driven by	<input type="checkbox"/>	Electric motor	<input checked="" type="checkbox"/>	Driven rating / speed	(*)	kW / RPM			
21	<input checked="" type="checkbox"/>	Engine driven water circulating (*)									
22	<input checked="" type="checkbox"/>	Engine water inlet / outlet temperature (*) °C									
23	<input type="checkbox"/>	Open circuit cooling with engine driven water circulating pump (*)									
24	<input checked="" type="checkbox"/>	Close circuit cooling including									
25	<input checked="" type="checkbox"/>	Primary (soft) Circuit piping with temperature control & make - up tank									
26	<input checked="" type="checkbox"/>	Jockey water pump	<input checked="" type="checkbox"/>	Yes	<input type="checkbox"/>	No					
27		Drive	(*)	Capacitor	(*)	m ³ hr	Head	(*)	Seal	(*)	
28		Speed	(*)	Impeller material	(*)	Case	(*)	MFR	(*)	Model	(*)
29	<input checked="" type="checkbox"/>	Heat Exchanger with anchor / foundation bolts									
30	<input checked="" type="checkbox"/>	Secondary water CKT piping with		<input checked="" type="checkbox"/>	Check valve	<input checked="" type="checkbox"/>	Strainers	<input checked="" type="checkbox"/>	PR. regulators	<input checked="" type="checkbox"/>	Bypass valve
31	<input checked="" type="checkbox"/>	Heat Exchanger inlet / outlet temperat (Primary circuit) (*)									
32											
33	FRAME LUBRICATING SYSTEM										
34	<input type="checkbox"/>	Splash lubrication									
35	<input checked="" type="checkbox"/>	Oil Pump <input checked="" type="checkbox"/> Integral <input checked="" type="checkbox"/> Separate type									
36		Drive	(*)	Capacitor	(*)	Pressure	(*)	Speed	(*)		
37		Impeller or gear matl	(*)	Case matl.	(*)	MFR	(*)	Model	(*)		
38	<input checked="" type="checkbox"/>	Pre - lub pump	<input checked="" type="checkbox"/>	Yes	<input type="checkbox"/>	No	Type	(*)	Drive min. circ	(*)	m ³ /hr
39	<input checked="" type="checkbox"/>	Oil Filter	<input checked="" type="checkbox"/>	Yes	<input type="checkbox"/>	No	Type	(*)	Filter to	(*)	Microns
40	<input checked="" type="checkbox"/>	Oil level controllers	Lubricator	<input checked="" type="checkbox"/>	Yes	<input type="checkbox"/>	No	MFR	(*)	Model	(*)
41		Crankcase		<input checked="" type="checkbox"/>	Yes	<input type="checkbox"/>	No	MFR	(*)	Model	(*)
42	<input checked="" type="checkbox"/>	Oil cooler	No.	(*)	Manufacture	(*)	Type	(*)			
43		Duty	(*)	kW/hr	Surface	(*)	m ²	Code	(*)		
44		Shell	(*)	mm	Thickness	(*)	mm	Design pressure	(*)		
45		Tubes	(*)	mm	Length	(*)	m	No.	(*)		
46	Note:										
47	1	Air cooled heat exchanger shall be supplied									
48	2	(*) Vendor to advise									
49											
50											
51											
52											
53											
54											
55											
56											
57											
58											
59											
60											
61											
62											
63											



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 7 of 12

DATASHEET FOR DIESEL GENERATOR

FUEL SYSTEM												
1												
2	<input checked="" type="checkbox"/> Gravity FEED system											<input type="checkbox"/> Fuel lift pump
3	<input checked="" type="checkbox"/> Fuel Filters	<input type="checkbox"/> Paper cartridge									<input checked="" type="checkbox"/> Duplex	
4	<input checked="" type="checkbox"/> Fuel injection pump	<input checked="" type="checkbox"/> Make (*)									<input checked="" type="checkbox"/> Model (*)	
5	Daily diesel oil fuel tank	<input type="checkbox"/> Engine mounted		<input type="checkbox"/> Wall mounted					<input checked="" type="checkbox"/> Skid mounted			
6	Capacity litres	<input type="checkbox"/> For 24 hours									<input checked="" type="checkbox"/> 8 hours	
7	Diesel oil fuel tank, Capacity	<input type="checkbox"/> For two weeks									<input type="checkbox"/> For one week	
8	Fuel transfer pump	<input type="checkbox"/> Type (*)		<input type="checkbox"/> Make (*)					<input type="checkbox"/> Driven by			
9	<input checked="" type="checkbox"/> Fuel piping and fittings											
10	Daily tank to engine	<input type="checkbox"/> Transfer pumps to daily tank							<input checked="" type="checkbox"/> Overflow pipes			
11	<input checked="" type="checkbox"/> All others piping, fittings and valve etc..											
12												
13	- Fuel system shall be designed in a manner that no air locks or air traps are formed											
14												
OTHER AUXILIARY EQUIPMENT												
15												
16	Exh. Silence	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> Spark arrester	<input type="checkbox"/> STD. Comm. / Hosp. Silencing MFR			Model (*)				
17	Mounting	<input checked="" type="checkbox"/> Horizontal		<input checked="" type="checkbox"/> Vertical		<input type="checkbox"/> Saddles		<input type="checkbox"/> Trunnions		<input type="checkbox"/> Other		
18	Exhaust manifold	<input type="checkbox"/> Wet		<input checked="" type="checkbox"/> Dry		<input checked="" type="checkbox"/> Insulated		<input checked="" type="checkbox"/> Shielded		Material (*)		
19	Air Filter	<input checked="" type="checkbox"/> Yes		<input type="checkbox"/> No		Type		<input checked="" type="checkbox"/> Dry		<input checked="" type="checkbox"/> Oil bath MFP (*) Model (*)		
20	Connection	<input checked="" type="checkbox"/> Side		<input type="checkbox"/> Top		<input type="checkbox"/> Bottom		Max. intake air restriction allowabl (*) mm Hg				
21	Fly wheel barring	<input checked="" type="checkbox"/> Manual (*)		<input type="checkbox"/> Air jack (*)								
22	Fly wheel Guard	<input checked="" type="checkbox"/> Yes		<input type="checkbox"/> No		Type (*)						
23	Gear Unit	MFR (*)		Type (*)		Rating (*)		kW				
24	Agnate service factor	(*)		Mech. Efficiency		(*)		Other				
25	Gears pitch diameter	(*)		With		(*)		Material (*)				
26												
MATERIAL OF CONSTRUCTION												
27												
28	Charge air coolers	(*)		Shell		(*)		Tubes		(*)		
29	Water cooler	(*)		Shell		(*)		Tubes		(*)		
30	Air cooler	(*)		Shell		(*)		Tubes		(*)		
31	Air receiver	(*)										
32	Fuel tank	(*)		Cry head		(*)		Crankshaft		(*)		
33	Connecting road	(*)		Main bearings		(*)		Valve		(*)		
34	Connection road bolts	(*)		Piton rings		(*)						
35												
INSTRUMENTATION												
36												
37	Tachometer	<input type="checkbox"/> Mechinal		<input checked="" type="checkbox"/> Electric				<input type="checkbox"/> Other				
38	Make		(*)		Model		(*)					
39	Pyrometer required	<input checked="" type="checkbox"/> Yes		<input type="checkbox"/> No		No. point		Make		(*) Model (*)		
40	Engine gauge board furnished with	<input checked="" type="checkbox"/> Pyrometer		<input checked="" type="checkbox"/> Tachometer		<input checked="" type="checkbox"/> Oil press. Gauge		<input checked="" type="checkbox"/> Oil temp. gauge				
41	<input type="checkbox"/> J.W temp. gauge		<input checked="" type="checkbox"/> Fuel press. Gauge		<input type="checkbox"/> Air press. Gauge		<input checked="" type="checkbox"/> Time digital meter		<input checked="" type="checkbox"/> Day tank level			
42												
ALARM AND SAFETY SHUTDOWN												
43												
44	Condition	Alarm	S.P	Annunc.	S.D	S.P	Condition	Alarm	S.P	Annunc.	S.D	S.P
45	Overspeed	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input checked="" type="checkbox"/>		High J.W. temp.	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	
46	Low L.O Press.	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>		Low water level	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>	
47	Low air press.	<input type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>		Eng. Fails to start	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input checked="" type="checkbox"/>	
48	Low Fuel level	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input checked="" type="checkbox"/>		High exh. Gas temp	<input checked="" type="checkbox"/>		<input checked="" type="checkbox"/>	<input type="checkbox"/>	
49	High vibration	<input checked="" type="checkbox"/>		<input type="checkbox"/>	<input type="checkbox"/>							
50												
51	Note:											
52	1 (*) Vendor to advise											
53												
54												
55												
56												
57												
58												
59												
60												
61												



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 8 of 12

DATASHEET FOR DIESEL GENERATOR

CONNECTION										
SERVICE	No.	SIZE	RATING	TYPE	SERVICE	No.	SIZE	RATING	TYPE	
Exhaust	(*)	(*)	(*)	(*)	J. W Inlet					
Air inlet	(*)	(*)	(*)	(*)	J.W outlet					
Starting air					Oil inlet	(*)	(*)	(*)	(*)	
					Oil outlet	(*)	(*)	(*)	(*)	

INSPECTION AND TEST					ERECTION & MAINTERNANCE					
					Required Not required					
Shop inspection				<input type="checkbox"/>	<input checked="" type="checkbox"/>	Net weight of engine with mounted ancillaries			(*)	kgs
Full load test and overload test				<input checked="" type="checkbox"/>	<input type="checkbox"/>	Maximum weight to be handled during erection			(*)	kgs
Fuel consumption and governing test				<input checked="" type="checkbox"/>	<input type="checkbox"/>	Change of lubricating oil after			(*)	hours
Auxiliary equipment test				<input checked="" type="checkbox"/>	<input type="checkbox"/>	Expected period of running between main overhauls			(*)	hours
Control panel functional test				<input checked="" type="checkbox"/>	<input type="checkbox"/>	Expected period of running between top overhauls			(*)	hours
Sound level test				<input checked="" type="checkbox"/>	<input type="checkbox"/>					
Complete unit test (with driven equipment)				<input checked="" type="checkbox"/>	<input type="checkbox"/>					
Extinguisher test				<input type="checkbox"/>	<input checked="" type="checkbox"/>					

18

19 **Note:**

20 1 (*) Vendor to advise

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 9 of 12

DATASHEET FOR DIESEL GENERATOR

A.C SYNCHRONOUS GENERATOR DATA

A. ELECTRICAL SPECIFICATION

1	Specification		25	Parallel Operation	No
2	Drawing unit		26	Excitation system	
3	Rated output (at Site conditions)	455 kVA at 0.8 p.f lagging		a. Type	Brushless
4	Voltage	380 V, 3 phases, 4 wires		b. Grade	(to BS 4999 pt. 140)
5	Frequency	50Hz ±1%		c. Control	Auto voltage regulator
6	Duty type	Continuous capacity		d. Auto follower	(*)
7	Rating class	Max. continuous (to BS 4999 pt 101)		e. Field suppression	Yes
8	Design	Synchronous		f. M/C volts adjust	+ (*) % - (*) of Volts
9	Synch. Speed	1500 rpm		g. Quad drop adjust	+ (*) % - (*) of Volts
10	Phase sequence	R.T.S		h. Monitoring	Diode failre No
11	System max. short circuit level	(*) kA RMS symmetrical (*) kA peak			Over/Under voltage Yes
12	Generator max. short circuit contribution	(*) kA RMS symmetrical (*) kA peak			Over/Under excitation Limits
13	Motor starting		27	Main terminal box	Power factor control Yes
	a. Initial load	(*) kVA at (*) P.F		a. Type	(*)
	b. Starting load	(*) kVA at (*) P.F		b. Termination type	(*)
	c. Max. Voltage dip.	15% of rated voltage		c. Entry	(*)
14	Degree of protection			d. Cable	2xCu/XLPE/DSTA/PVC(3x240+1x120)
	a. Gen. / Exciter	IP 31 (min.)	28	Neutral terminal box	Including in main terminal box
	b. Main / Netral boxes	IP 31 (min.)		a. Type	(*)
	c. Aux. Term. Boxes	IP 31 (min.)		b. Termination type	(*)
	d. Enclosure	IP 31 (min.)		c. Entry	Bottom
15	Gen. Neutral earthing	Solid		d. Cable	(*)
	a. Type	Copper	29	Current transformers	
	b. Impedance	(*) Ohms		a. Free issue	(*)
16	Short Circuit support	(*) x FLC for 1 sec. (From rated design temperature)		b. By vendor	(*)
17	Stator connection	STAR / DELTA (*)	30	Location	PETEC Hai Phong
18	Noise limit	85 Db at 1 metre	31	Ambient temperature	
19	Winding Insulation class	F		a. Design	Max. 45 °C min. 5.4 °C
20	Max. temp. rise class	B		b. Site	Max. 42.0 °C min. 5.4 °C
21	Cooling method	(at °C inlet temperature)	32	Max. relative humidity	95% (Outdoor)
	a. Type	(*)	33	Altitude	< 1000 m
	b. Design refer	(to BS 4999 pt 106)	34	Site environment	Humid, Tropical
	c. Exchanger Rating	No	35	Explosion protection	Non - hazaduous Area
	d. Primaty coolant	No		a. Generator	
	e. Secondary coolant	No		b. Terminal box	
	f. Flow limitation	No	36	Anti - connection heater	
22	Temperature Detectors			a. Generator	(*) volts 50 Hz
	a. Bearing	No		b. Terminal box	(*) volts 50 Hz
	b. Stator winding	(Embedded)			
23	Vibration limit	(*)			
24	Vibration detector	(*)			

Note:

- 1 (*) Vendor to advise
- 2 Vendor shall be advise transient response of machine terminal voltage the motor starting condition
- 3 The automatic voltage regulator power factor control card will be used for automatic voltage regulator shedding during normal shutdown
- 4 Vendor to update rated output based on the power energy balance document



THIẾT KẾ CƠ SỞ
DỰ ÁN: MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU
PETEC HẢI PHÒNG



Số tài liệu: PTHP-EL-DAS-001

Sheet: 12 of 12

DATASHEET FOR DIESEL GENERATOR

LOW PRESSURE AND ATMOSPHERIC TANK

		Diesel	NOZZLE & CONNECTIONS					
		(*)	Make	Service	No.	Size	Rating	Facing
1	Product stored	Diesel						
2	Density	(*)						
3	Capacity (working capacity equivalent to 8 hrs running at full load)	(*)	C1	Fill	1	(*)		
4	Operating pressure	Atmospheric	C2	Fuel outlet	1	(*)		
5	Operating temperature	Ambient	C3	Fuel return	1	(*)		
6	Design pressure	(*)	C4	Over flow	1	(*)		
7	Design temperature	(*)	C5	Vent	1	(*)		
8	Maximum allowable working pressure	(*)	C6	Drain (valve and Blanked	1	(*)		
9	Hydraulic test pressure	(*)	R1	Level Gauge	1		(*)	
10	Stress relief	No	R2	Level Switch low	1		(*)	
11	Radiography	No						
12	Other test	100% visual, 100% MPI						
13	Total volume	(*)						
14	Normal liquid volume	(*)						
15	Fabricated weight	(*)						
16	Test weight	(*)						
17	Inspection	(*)						
18	Insullation	(*)						
19	Surface preparation	(*)						
20	Surface finish	(*)						
21	Internal coating	Yes						
22	Material	(*)						
23	Shell	(*)						
24	Roof	(*)						
25	Base	(*)						
26	Structurals	(*)						
27	Nozzles	(*)						
28	Flangers	(*)						
29	Studs	(*)						
30	Gaskets	(*)						
31	Internals	(*)						

Note:

1 (*) Vendor to advise

32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62

	* GHI CHÚ ACB : MÁY CẮT KHÔNG KHÍ MCCB : MÁY CẮT DẠNG KHỐI MCB : MÁY CẮT DẠNG TẾP		ĐỒNG HỒ ĐA CHỨC NĂNG (V, A, Hz, W, VA, VAC, PF...)
	CẦU CHÌ HẠ THẾ		CÔNG TẮC TỰ
	MÁY BIẾN DÒNG		TỦ ĐIỆN NHÀ CUNG CẤP
	ĐÈN BÁO PHA (LED) * CHỈ THỊ MÀU R : ĐỎ Y : VÀNG B : XANH		PHẠM VI CÔNG VIỆC
	CÁP ĐIỆN		TRẠM ĐIỀU KHIỂN TẠI CHỖ (LCS)
	CÁP TÍN HIỆU ĐIỀU KHIỂN		MÁY PHÁT ĐIỆN
	DỰ PHÒNG		THIẾT BỊ LỌC VÀ CẮT SÉT LAN TRUYỀN
	NỐI ĐẤT		
	THIẾT BỊ ĐO DÒNG ĐIỆN		
	THIẾT BỊ ĐO ĐIỆN ÁP		
	BỘ KHỞI ĐỘNG TRỰC TIẾP		
	BỘ KHỞI ĐỘNG MỀM		
	BỘ BIẾN TẦN		

GHI CHÚ:

- Tất cả kích thước và cao độ sử dụng là mm nếu không có ghi chú khác.
- Phần bản vẽ hiện trạng và các hệ thống hiện hữu căn cứ vào tài liệu do xí nghiệp xăng dầu PETEC Hải Phòng cung cấp.
- Phần điện cho các nhà mở rộng đấu nối vào hệ thống điện hiện hữu tại nhà đó.
- Các thiết bị của hệ thống điện động lực mới phải tương thích hoàn toàn với hệ thống hiện hữu để đấu nối vào.
- MCCB dùng loại phù hợp với tải cần bảo vệ, có bảo vệ quá tải và ngắn mạch, chỉnh được dòng bảo vệ quá tải.
- Hệ thống tiếp địa cho tủ điện và thiết bị điện phải có giá trị điện trở tiếp địa luôn nhỏ hơn hay bằng 4Ω.
- Bổ sung thêm vào tủ tổng T2 hiện hữu 4 MCCB cấp nguồn cho các tải mở rộng.
- Cải tạo tủ T5 hiện hữu: thay các MCCB cho phù hợp với công suất bơm PCCC mới, bổ sung biến tần cho các bơm, bơm PCCC hoạt động theo chế độ 1 bơm chạy và 1 bơm dự phòng, tổng công suất điện các bơm PCCC mới ở chế độ vận hành lớn nhất (1 bơm nước và 1 bơm foam) bằng công suất điện hệ thống hiện hữu (tài liệu PETEC cung cấp).

-		
-		
A	11/09/2025	XEM XÉT, GÓP Ý CỦA CHỦ ĐẦU TƯ

LẦN	NGÀY	MỤC ĐÍCH
CHỦ ĐẦU TƯ		
TỔNG CÔNG TY THƯƠNG MẠI KỸ THUẬT VÀ ĐẦU TƯ - CTCP		
 194 NAM KỶ KHÔI NGHĨA, P. XUÂN HÒA, TP. HỒ CHÍ MINH		

LIÊN DANH NHÀ THẦU EPC		

ĐƠN VỊ TƯ VẤN THIẾT KẾ		
CÔNG TY CP TM XD VÀ THIẾT KẾ PHƯƠNG ANH		
237 ĐƯỜNG NAM HÒA, P. PHƯỚC LONG, TP. HỒ CHÍ MINH		
GIÁM ĐỐC		

ĐINH VĂN TÁNH		
---------------	--	--









C.N.T.K	Phạm Văn Khương	
KIỂM SOÁT	Lê Minh Cảnh	
CHỦ TRÌ TK	Lê Minh Cảnh	
THIẾT KẾ	Tôn Thất Huy	

TÊN DỰ ÁN
MỞ RỘNG SỨC CHỨA 40.000m³
KHO XĂNG DẦU PETEC HẢI PHÒNG
 ĐỊA ĐIỂM XÂY DỰNG
 KHU HẠ ĐOẠN 2, P. ĐÔNG HẢI, TP. HẢI PHÒNG

HANG MỤC
TỔNG MẶT BẰNG

TÊN BẢN VẼ
 KÝ HIỆU VÀ CHÚ THÍCH CHO SƠ ĐỒ
 NGUYÊN LÝ HỆ THỐNG ĐIỆN ĐỘNG LỰC

GIẢI ĐOẠN: T.K.K.T	TỶ LỆ: -	TỜ/SỐ TỜ: 01/02
SỐ BẢN VẼ PTSC.TH.DD.PA-PETEC-EL-DWG-00-001	KHỔ A2	LẦN A



- GHI CHÚ:**
- Tất cả kích thước và cao độ sử dụng là mm nếu không có ghi chú khác.
 - Phần bản vẽ hiện trạng và các hệ thống hiện hữu căn cứ vào tài liệu do xí nghiệp xăng dầu PETEC Hải Phòng cung cấp.
 - Phần điện cho các nhà mở rộng đầu nối vào hệ thống điện hiện hữu tại nhà đó.
 - Các thiết bị của hệ thống điện động lực mới phải tương thích hoàn toàn với hệ thống hiện hữu để đầu nối vào.
 - MCCB dùng loại phù hợp với tải cần bảo vệ, có bảo vệ quá tải và ngắn mạch, chỉnh được dòng bảo vệ quá tải.
 - Hệ thống tiếp địa cho tủ điện và thiết bị điện phải có giá trị điện trở tiếp địa luôn nhỏ hơn hay bằng 4Ω.
 - Bổ sung thêm vào tủ tổng T2 hiện hữu 5 MCCB cấp nguồn cho các tải mở rộng.
 - Cải tạo tủ T5 hiện hữu: thay các MCCB cho phù hợp với công suất bơm PCCC mới, bổ sung biến tần cho các bơm, bơm PCCC hoạt động theo chế độ 1 bơm chạy và 1 bơm dự phòng, tổng công suất điện các bơm PCCC mới ở chế độ vận hành lớn nhất (1 bơm nước và 1 bơm foam) bằng công suất điện hệ thống hiện hữu (tài liệu PETEC cung cấp).

-		
-		
A	11/09/2025	XEM XÉT, GÓP Ý CỦA CHỦ ĐẦU TƯ
LÀN	NGÀY	MỤC ĐÍCH
CHỦ ĐẦU TƯ		
TỔNG CÔNG TY THƯƠNG MẠI KỸ THUẬT VÀ ĐẦU TƯ - CTCP		
PETROVIETNAM		
194 NAM KỶ KHÔI NGHĨA, P. XUÂN HÒA, TP. HỒ CHÍ MINH		

LIÊN DANH NHÀ THẦU EPC

PTSC THANH HÒA **DAI DUNG** **PHƯƠNG ANH**

ĐƠN VỊ TƯ VẤN THIẾT KẾ

CÔNG TY CP TM XD VÀ THIẾT KẾ PHƯƠNG ANH

237 ĐƯỜNG NAM HÒA, P. PHƯỚC LONG, TP. HỒ CHÍ MINH

GIÁM ĐỐC

ĐINH VĂN TÁNH

C.N.T.K	Phạm Văn Khương	<i>[Signature]</i>
KIỂM SOÁT	Lê Minh Cảnh	<i>[Signature]</i>
CHỦ TRÌ TK	Lê Minh Cảnh	<i>[Signature]</i>
THIẾT KẾ	Tôn Thất Huy	<i>[Signature]</i>

TÊN DỰ ÁN

MỞ RỘNG SỨC CHỨA 40.000m³

KHO XĂNG DẦU PETEC HẢI PHÒNG

ĐỊA ĐIỂM XÂY DỰNG

KHU HẠ ĐOẠN 2, P. ĐỒNG HẢI, TP. HẢI PHÒNG



HANG MỤC

TỔNG MẶT BẰNG

TÊN BẢN VẼ



SƠ ĐỒ NGUYÊN LÝ HỆ THỐNG ĐIỆN ĐỘNG LỰC

GIẢI ĐOẠN: T.K.K.T	TỶ LỆ: -	TỜ/SỐ TỜ: 02/02
SỐ BẢN VẼ	PTSC/TH.DD.PA-PETEC-EL-DWG-00-001	KHỒ LÀN
		A2 A

	<p align="center">EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG</p>	
<p align="center">TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR</p>		<p>Tài liệu số: TRD-004</p>
		<p>Phiên bản số: A</p>

**ATTACHMENT #3
TECHNICAL BID PROPOSAL**

- *Att #3.1 Technical Bid Requirement*
- *Att #3.2 Technical Bid forms*
- *Att #3.3 Technical Bid Clarification*

	<p align="center">EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG</p>	
<p align="center">TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR</p>		<p>Tài liệu số: TRD-004</p>
		<p>Phiên bản số: A</p>

**ATTACHMENT #4
SUPPLIER/ BIDDER DATA DOCUMENTS LIST**

VENDOR DATA DOCUMENTS

Legend:

1* : E

E : Electronic file

PO + XXD: XX days after PO date

DE – YYD: YY days before delivery date

IFI: Issued for Information

*2 : 1OR + 9C + E + 2CD

C : Copy CD : CD-ROM

OR : Original

IFR: Issued for Review

VD Code	Description	With Bid	Stage	First Issue			Final Issue
				Issue Date	Purpose	Quantity/ Type	Quantity/ Type
1	Vendor Data Index & Schedule	E	Procurement	PO+14D	IFR	*1	*2
2	Engineering, Procurement, Manufacturing & Test Schedule	E	Procurement	PO+14D	IFR	*1	*2
3	Warranty / Guarantee Confirmation	E	Procurement	PO+14D	IFR	*1	*2
14	Lifting / Transport Drawings	E	Procurement	PO+14D	IFR	*1	*2
29	Recommended Spare Parts List (Start-up & 2 years)	E	Procurement	PO+14D	IFR	*1	*2
30	Special Tools List	E	Procurement	PO+14D	IFR	*1	*2
31	Preservation & Storage Procedure	E	Procurement	PO+14D	IFR	*1	*2
4	Packing List	E	Logistics	PO+14D	IFR	*1	*2
5	Commercial Invoice	E	Logistics	PO+14D	IFR	*1	*2
6	Bill of Lading / Airway Bill	E	Logistics	PO+14D	IFR	*1	*2
7	Insurance Certificate	E	Logistics	PO+14D	IFR	*1	*2
8	Certificate of Origin (CO)	E	Delivery	PO+14D	IFR	*1	*2
9	Certificate of Quality (CQ)	E	Delivery	PO+14D	IFR	*1	*2
10	Equipment Data Sheet (Diesel Generator)	E	Design	PO+14D	IFR	*1	*2
11	Foundation Load & Anchor Bolt Location	E	Design	PO+14D	IFR	*1	*2
12	General Arrangement Drawings	E	Design	PO+14D	IFR	*1	*2
13	Noise Level Data Sheet	E	Design	PO+14D	IFR	*1	*2
15	Piping & Instrument Diagrams (Fuel, Cooling, Exhaust)	E	Design	PO+14D	IFR	*1	*2
16	Electrical Single Line Diagram (DG Panel & MCC)	E	Design	PO+14D	IFR	*1	*2
17	Wiring & Termination Drawings	E	Design	PO+14D	IFR	*1	*2
18	Control & Protection Philosophy	E	Design	PO+14D	IFR	*1	*2
19	Alarm & Trip Set Point List	E	Design	PO+14D	IFR	*1	*2
20	Panel Layout & Schematics	E	Design	PO+14D	IFR	*1	*2
21	Cause & Effect Chart	E	Design	PO+14D	IFR	*1	*2
22	Inspection & Test Plan (ITP)	E	Manufacturing	PO+14D	IFR	*1	*2
23	Factory Acceptance Test Procedure	E	FAT	PO+14D	IFR	*1	*2
24	FAT Report	E	FAT	PO+14D	IFR	*1	*2

VENDOR DATA DOCUMENTS

Legend:

1* : E

E : Electronic file

PO + **XXD**: XX days after PO date

DE – **YYD**: YY days before delivery date

IFI: Issued for Information



*2 : 1OR + 9C + E + 2CD

C : Copy CD : CD-ROM

OR : Original

IFR: Issued for Review

VD Code	Description	With Bid	Stage	First Issue			Final Issue
				Issue Date	Purpose	Quantity/ Type	Quantity/ Type
25	Site Acceptance Test (SAT) Procedure	E	Commissioning	PO+14D	IFR	*1	*2
26	SAT Report	E	Commissioning	PO+14D	IFR	*1	*2
27	Installation, Operation & Maintenance Manual (IOM)	E	Handover	PO+14D	IFR	*1	*2
28	Training Manuals (O&M)	E	Handover	PO+14D	IFR	*1	*2



	<p align="center">EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG</p>	
<p align="center">TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR</p>		<p>Tài liệu số: TRD-004</p>
		<p>Phiên bản số: A</p>

**ATTACHMENT #5
TYPICAL INSPECTION AND TEST PLAN**

TYPICAL INSPECTION AND TEST PLAN

Legend:
R: Responsibility
W: Witness

Code	Inspection Item	PURCHASER	OWNER	3rd Party Inspection
1	Vendor Document	R	R	-
2	Receiving Inspection	R	R	-
3	Fabrication Center Leak test	W	W	R
4	Ratio & Assembly Inspection, Including Phase Relation and Polarity	W	W	R
5	Resistance Inspection	W	W	R
6	Insulation Power Factor Test	W	W	R
7	MeggerTest	W	W	R
8	ImpulSe Test	W	W	R
9	Applied Potential (Hipot) Test	W	W	W
10	Induced Potential Test	W	W	R
11	No-load Loss Test	W	W	W
12	Loss and Impedance Test	W	W	R
13	Continuity Test	W	W	-
14	Leak Test	W	W	R
15	Final Inspection	W	W	R
16	Paint & Pallet Inspection	W	W	-
17	Final Documentation Review	W	W	-
18	Preshipment Inspection	W	W	-
19	Inspection Release Note	W	W	-
20	Dimensional check and visual inspection	R	R	-
21	N.D.E	R	R	R
22	Mechanical running test - Noise, Vibration, Temp. rising check, etc.	W	W	R

	<p align="center">EXPANSION OF 40,000M³ STORAGE CAPACITY AT PETEC HAI PHONG</p>	
<p align="center">TECHNICAL REQUISITION DOCUMENT FOR DIESEL GENERATOR</p>		<p>Tài liệu số: TRD-004</p>
		<p>Phiên bản số: A</p>

**ATTACHMENT #6
PROJECT SCHEDULE**



DỰ ÁN MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG

Phụ lục 3 - Tiến Độ Thực Hiện



Activity ID	Activity Name	Original Duration	Start	Finish	2025												2026												2027
					Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan					
MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG - Sub					24-Jul-26																								
CÁC MỐC DỰ ÁN CHÍNH					24-Jul-26																								
PETEC.KEY0001	Ngày ký hợp đồng	0d	12-Aug-25*		◆ Ngày ký hợp đồng																								
PETEC.KEY0005	Thẩm định hồ sơ thiết kế của Bộ Công thương (*)	0d		18-Sep-25	◆ Thẩm định hồ sơ thiết kế của Bộ Công thương (*)																								
PETEC.KEY0010	Thẩm duyệt thiết kế PCCC (*)	30d	24-Aug-25	22-Sep-25	24-Aug-25 [] 22-Sep-25																								
PETEC.KEY0020	Xin phép xây dựng (*)	30d	01-Oct-25	30-Oct-25	01-Oct-25 [] 30-Oct-25																								
PETEC.KEY1010	ENG - Công tác thiết kế	60d	12-Aug-25	10-Oct-25	12-Aug-25 [] 10-Oct-25																								
PETEC.KEY1020	PRO - Công tác mua sắm	180d	30-Aug-25	25-Feb-26	30-Aug-25 [] 25-Feb-26																								
PETEC.KEY1025	HO - Bàn giao mặt bằng (**)	0d		27-Aug-25	◆ HO - Bàn giao mặt bằng (**)																								
PETEC.KEY1050	CON - Công tác xây lắp	285d	11-Sep-25	22-Jun-26	11-Sep-25 [] 22-Jun-26																								
PETEC.KEY1055	MC - Hoàn thành cơ khí	0d		22-Jun-26	◆ MC - Hoàn thành cơ khí																								
PETEC.KEY1060	COM - Nghiệp thu bàn giao đưa vào sử dụng	74d	12-May-26	24-Jul-26	12-May-26 [] 24-Jul-26																								
PETEC.KEY1070	Nghiệm thu hoàn công Nhà Nước (*)	0d		28-Aug-26	◆ Nghiệm thu hoàn công Nhà Nước (*)																								
THIẾT KẾ					12-Aug-25 [] 10-Oct-25																								
CÔNG TÁC CHUNG					12-Aug-25 [] 18-Aug-25																								
PETEC.ENG.1070	ENG - Danh mục tài liệu thiết kế (EMDR)	7d	12-Aug-25	18-Aug-25	12-Aug-25 [] 18-Aug-25																								
THIẾT KẾ CHI TIẾT					12-Aug-25 [] 10-Oct-25																								
THIẾT KẾ CỌC					12-Aug-25 [] 09-Oct-25																								
PETEC.ENG.1080	Tính toán và thiết kế cọc thử	10d	12-Aug-25	21-Aug-25	12-Aug-25 [] 21-Aug-25																								
PETEC.ENG.1210	Cập nhật thiết kế cọc đại trà	3d	02-Oct-25	04-Oct-25	02-Oct-25 [] 04-Oct-25																								
PETEC.ENG.1220	Cập nhật MTO cho cọc đại trà	5d	05-Oct-25	09-Oct-25	05-Oct-25 [] 09-Oct-25																								
CSA					12-Aug-25 [] 10-Oct-25																								
PETEC.ENG.1000	Chuẩn bị tài liệu kỹ thuật	20d	12-Aug-25	31-Aug-25	12-Aug-25 [] 31-Aug-25																								
PETEC.ENG.1150	Thiết kế chi tiết	30d	01-Sep-25	30-Sep-25	01-Sep-25 [] 30-Sep-25																								
PETEC.ENG.1230	Ban hành TRD cho công tác lựa chọn Nhà thầu	10d	01-Oct-25	10-Oct-25	01-Oct-25 [] 10-Oct-25																								
CÔNG NGHỆ					12-Aug-25 [] 30-Sep-25																								
PETEC.ENG.1010	Chuẩn bị tài liệu kỹ thuật	20d	12-Aug-25	31-Aug-25	12-Aug-25 [] 31-Aug-25																								
PETEC.ENG.1160	Thiết kế chi tiết	30d	01-Sep-25	30-Sep-25	01-Sep-25 [] 30-Sep-25																								
ĐƯỜNG ỐNG					12-Aug-25 [] 10-Sep-25																								
PETEC.ENG.1020	Chuẩn bị tài liệu kỹ thuật	10d	12-Aug-25	21-Aug-25	12-Aug-25 [] 21-Aug-25																								
PETEC.ENG.1100	Thiết kế chi tiết	15d	22-Aug-25	05-Sep-25	22-Aug-25 [] 05-Sep-25																								
PETEC.ENG.1170	Phát hành MTO cho công tác mua sắm	5d	06-Sep-25	10-Sep-25	06-Sep-25 [] 10-Sep-25																								
THIẾT BỊ					12-Aug-25 [] 14-Sep-25																								
PETEC.ENG.1030	Chuẩn bị tài liệu kỹ thuật	10d	12-Aug-25	21-Aug-25	12-Aug-25 [] 21-Aug-25																								
PETEC.ENG.1110	Thiết kế chi tiết	20d	22-Aug-25	10-Sep-25	22-Aug-25 [] 10-Sep-25																								
PETEC.ENG.1200	Phát hành MTO cho công tác mua sắm	4d	11-Sep-25	14-Sep-25	11-Sep-25 [] 14-Sep-25																								
BỒN					12-Aug-25 [] 29-Aug-25																								
PETEC.ENG.1040	Chuẩn bị tài liệu kỹ thuật	5d	12-Aug-25	16-Aug-25	12-Aug-25 [] 16-Aug-25																								
PETEC.ENG.1090	Thiết kế chi tiết	10d	17-Aug-25	26-Aug-25	17-Aug-25 [] 26-Aug-25																								
PETEC.ENG.1140	Phát hành MTO cho công tác mua sắm	3d	27-Aug-25	29-Aug-25	27-Aug-25 [] 29-Aug-25																								
ĐIỆN					12-Aug-25 [] 10-Sep-25																								

█ Critical Path ◆ Milestone
█ Actual Work ▬ Summary
█ Remaining Work
█ Critical Remaining Work

Page 1 of 12

(*) Thời gian thực hiện các công việc này không nằm trong thời gian thực hiện hợp đồng, nhưng không quá thời gian theo quy định.

(**) Đây là ngày bàn giao mặt bằng dự kiến, cần cử vào ngày bàn giao thực tế của CĐT Nhà thầu sẽ cập nhật lại tiến độ và trình CĐT phê duyệt.

Date	Revision	Checked	Approved
04-May-25	Issue for Bidding	V.L.T	V.V.V
12-Aug-25	Issue for PO	V.L.T	V.V.V



DỰ ÁN MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG

Phụ lục 3 - Tiến Độ Thực Hiện



Activity ID	Activity Name	Original Duration	Start	Finish	2025												2026												2027
					Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan					
PETEC.ENG.1050	Chuẩn bị tài liệu kỹ thuật	10d	12-Aug-25	21-Aug-25	12-Aug-25 ■ 21-Aug-25																								
PETEC.ENG.1120	Thiết kế chi tiết	15d	22-Aug-25	05-Sep-25	22-Aug-25 ■ 05-Sep-25																								
PETEC.ENG.1180	Phát hành MTO cho công tác mua sắm	5d	06-Sep-25	10-Sep-25	06-Sep-25 ■ 10-Sep-25																								
ĐIỀU KHIỂN		44d	12-Aug-25	24-Sep-25	↔ 24-Sep-25																								
PETEC.ENG.1060	Chuẩn bị tài liệu kỹ thuật	10d	12-Aug-25	21-Aug-25	12-Aug-25 ■ 21-Aug-25																								
PETEC.ENG.1130	Thiết kế chi tiết	18d	22-Aug-25	08-Sep-25	22-Aug-25 ■ 08-Sep-25																								
PETEC.ENG.1190	Phát hành MTO cho công tác mua sắm	16d	09-Sep-25	24-Sep-25	09-Sep-25 ■ 24-Sep-25																								
3D BIM Modeling		7d	01-Oct-25	07-Oct-25	↘ 07-Oct-25																								
PETEC.ENG.1240	ENG - 90% 3D Modeling Review	7d	01-Oct-25	07-Oct-25	01-Oct-25 ■ 07-Oct-25																								
MUA SẮM		180d	30-Aug-25	25-Feb-26	↔ 25-Feb-26																								
VẬT TƯ BỒN BỂ		119d	30-Aug-25	26-Dec-25	↔ 26-Dec-25																								
Thép tấm bồn		42d	30-Aug-25	10-Oct-25	↔ 10-Oct-25																								
PETEC.PRO.1000	Ban hành TRD	7d	30-Aug-25	05-Sep-25	30-Aug-25 ■ 05-Sep-25																								
PETEC.PRO.1060	Đánh giá TBE	3d	06-Sep-25	08-Sep-25	06-Sep-25 ■ 08-Sep-25																								
PETEC.PRO.1090	Đánh giá CBE	2d	09-Sep-25	10-Sep-25	09-Sep-25 ■ 10-Sep-25																								
PETEC.PRO.1140	Ngày ký hợp đồng	2d	11-Sep-25	12-Sep-25	11-Sep-25 ■ 12-Sep-25																								
PETEC.PRO.1360	Ngày giao hàng đến công trường	28d	13-Sep-25	10-Oct-25	13-Sep-25 ■ 10-Oct-25																								
Thép kết cấu mái		42d	30-Aug-25	10-Oct-25	↔ 10-Oct-25																								
PETEC.PRO.1010	Ban hành TRD	7d	30-Aug-25	05-Sep-25	30-Aug-25 ■ 05-Sep-25																								
PETEC.PRO.1070	Đánh giá TBE	3d	06-Sep-25	08-Sep-25	06-Sep-25 ■ 08-Sep-25																								
PETEC.PRO.1100	Đánh giá CBE	2d	09-Sep-25	10-Sep-25	09-Sep-25 ■ 10-Sep-25																								
PETEC.PRO.1150	Ngày ký hợp đồng	2d	11-Sep-25	12-Sep-25	11-Sep-25 ■ 12-Sep-25																								
PETEC.PRO.1370	Ngày giao hàng đến công trường	28d	13-Sep-25	10-Oct-25	13-Sep-25 ■ 10-Oct-25																								
Thép kết cấu phụ kiện		41d	30-Aug-25	09-Oct-25	↔ 09-Oct-25																								
PETEC.PRO.1020	Ban hành TRD	7d	30-Aug-25	05-Sep-25	30-Aug-25 ■ 05-Sep-25																								
PETEC.PRO.1080	Đánh giá TBE	3d	06-Sep-25	08-Sep-25	06-Sep-25 ■ 08-Sep-25																								
PETEC.PRO.1110	Đánh giá CBE	2d	09-Sep-25	10-Sep-25	09-Sep-25 ■ 10-Sep-25																								
PETEC.PRO.1160	Ngày ký hợp đồng	1d	11-Sep-25	11-Sep-25	11-Sep-25 ■ 11-Sep-25																								
PETEC.PRO.1350	Ngày giao hàng đến công trường	28d	12-Sep-25	09-Oct-25	12-Sep-25 ■ 09-Oct-25																								
Mái phao bồn RON 95 10.000m3		119d	30-Aug-25	26-Dec-25	↔ 26-Dec-25																								
PETEC.PRO.1030	Ban hành TRD	10d	30-Aug-25	08-Sep-25	30-Aug-25 ■ 08-Sep-25																								
PETEC.PRO.1120	Đánh giá TBE	7d	09-Sep-25	15-Sep-25	09-Sep-25 ■ 15-Sep-25																								
PETEC.PRO.1440	Đánh giá CBE	2d	16-Sep-25	17-Sep-25	16-Sep-25 ■ 17-Sep-25																								
PETEC.PRO.1460	Ngày ký hợp đồng	2d	18-Sep-25	19-Sep-25	18-Sep-25 ■ 19-Sep-25																								
PETEC.PRO.1620	Ngày giao hàng đến công trường	98d	20-Sep-25	26-Dec-25	20-Sep-25 ■ 26-Dec-25																								
Vật tư ống và phụ kiện cho bồn bể		56d	30-Aug-25	24-Oct-25	↔ 24-Oct-25																								
PETEC.PRO.1040	Ban hành TRD	5d	30-Aug-25	03-Sep-25	30-Aug-25 ■ 03-Sep-25																								
PETEC.PRO.1050	Đánh giá TBE	5d	04-Sep-25	08-Sep-25	04-Sep-25 ■ 08-Sep-25																								
PETEC.PRO.1130	Đánh giá CBE	2d	09-Sep-25	10-Sep-25	09-Sep-25 ■ 10-Sep-25																								
PETEC.PRO.1170	Ngày ký hợp đồng	2d	11-Sep-25	12-Sep-25	11-Sep-25 ■ 12-Sep-25																								
PETEC.PRO.1380	Ngày giao hàng đến công trường	42d	13-Sep-25	24-Oct-25	13-Sep-25 ■ 24-Oct-25																								

- Critical Path
- Actual Work
- Remaining Work
- Critical Remaining Work
- ◆ Milestone
- ↔ Summary

Page 2 of 12

(*) Thời gian thực hiện các công việc này không nằm trong thời gian thực hiện hợp đồng, nhưng không quá thời gian theo quy định.
 (**) Đây là ngày bàn giao mặt bằng dự kiến, cần cử vào ngày bàn giao thực tế của CĐT Nhà thầu sẽ cập nhật lại tiến độ và trình CĐT phê duyệt.

Date	Revision	Checked	Approved
04-May-25	Issue for Bidding	V.L.T	V.V.V
12-Aug-25	Issue for PO	V.L.T	V.V.V



DỰ ÁN MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG

Phụ lục 3 - Tiến Độ Thực Hiện



Activity ID	Activity Name	Original Duration	Start	Finish	2025												2026												2027
					Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan					
KẾT CẤU					19-Nov-25																								
PETEC.PRO.2310	Ban hành TRD	5d	11-Oct-25	15-Oct-25	11-Oct-25 ■ 15-Oct-25																								
PETEC.PRO.2420	Đánh giá TBE	3d	16-Oct-25	18-Oct-25	16-Oct-25 ■ 18-Oct-25																								
PETEC.PRO.2670	Đánh giá CBE	2d	19-Oct-25	20-Oct-25	19-Oct-25 ■ 20-Oct-25																								
PETEC.PRO.2680	Ngày ký hợp đồng	2d	21-Oct-25	22-Oct-25	21-Oct-25 ■ 22-Oct-25																								
PETEC.PRO.2690	Ngày giao hàng đến công trường	28d	23-Oct-25	19-Nov-25	23-Oct-25 ■ 19-Nov-25																								
ĐƯỜNG ống					17-Jan-26																								
Vật tư đường ống và phụ kiện					26-Oct-25																								
PETEC.PRO.1180	Ban hành TRD	7d	11-Sep-25	17-Sep-25	11-Sep-25 ■ 17-Sep-25																								
PETEC.PRO.1470	Đánh giá TBE	5d	18-Sep-25	22-Sep-25	18-Sep-25 ■ 22-Sep-25																								
PETEC.PRO.1750	Đánh giá CBE	2d	23-Sep-25	24-Sep-25	23-Sep-25 ■ 24-Sep-25																								
PETEC.PRO.1840	Ngày ký hợp đồng	2d	25-Sep-25	26-Sep-25	25-Sep-25 ■ 26-Sep-25																								
PETEC.PRO.2020	Ngày giao hàng đến công trường	30d	27-Sep-25	26-Oct-25	27-Sep-25 ■ 26-Oct-25																								
Van công nghệ					19-Dec-25																								
PETEC.PRO.1190	Ban hành TRD	7d	11-Sep-25	17-Sep-25	11-Sep-25 ■ 17-Sep-25																								
PETEC.PRO.1480	Đánh giá TBE	5d	18-Sep-25	22-Sep-25	18-Sep-25 ■ 22-Sep-25																								
PETEC.PRO.1760	Đánh giá CBE	2d	23-Sep-25	24-Sep-25	23-Sep-25 ■ 24-Sep-25																								
PETEC.PRO.1850	Ngày ký hợp đồng	2d	25-Sep-25	26-Sep-25	25-Sep-25 ■ 26-Sep-25																								
PETEC.PRO.2030	Ngày giao hàng đến công trường	84d	27-Sep-25	19-Dec-25	27-Sep-25 ■ 19-Dec-25																								
Van an toàn					17-Jan-26																								
PETEC.PRO.1200	Ban hành TRD	7d	11-Sep-25	17-Sep-25	11-Sep-25 ■ 17-Sep-25																								
PETEC.PRO.1490	Đánh giá TBE	5d	18-Sep-25	22-Sep-25	18-Sep-25 ■ 22-Sep-25																								
PETEC.PRO.1770	Đánh giá CBE	2d	23-Sep-25	24-Sep-25	23-Sep-25 ■ 24-Sep-25																								
PETEC.PRO.2000	Ngày ký hợp đồng	2d	26-Sep-25	27-Sep-25	26-Sep-25 ■ 27-Sep-25																								
PETEC.PRO.2040	Ngày giao hàng đến công trường	112d	28-Sep-25	17-Jan-26	28-Sep-25 ■ 17-Jan-26																								
Bu lông và gioăng					25-Oct-25																								
PETEC.PRO.1210	Ban hành TRD	5d	11-Sep-25	15-Sep-25	11-Sep-25 ■ 15-Sep-25																								
PETEC.PRO.1450	Đánh giá TBE	3d	16-Sep-25	18-Sep-25	16-Sep-25 ■ 18-Sep-25																								
PETEC.PRO.1610	Đánh giá CBE	2d	19-Sep-25	20-Sep-25	19-Sep-25 ■ 20-Sep-25																								
PETEC.PRO.1990	Ngày ký hợp đồng	2d	26-Sep-25	27-Sep-25	26-Sep-25 ■ 27-Sep-25																								
PETEC.PRO.2050	Ngày giao hàng đến công trường	28d	28-Sep-25	25-Oct-25	28-Sep-25 ■ 25-Oct-25																								
Các chi tiết đặc biệt					06-Dec-25																								
PETEC.PRO.1220	Ban hành TRD	10d	11-Sep-25	20-Sep-25	11-Sep-25 ■ 20-Sep-25																								
PETEC.PRO.1630	Đánh giá TBE	3d	21-Sep-25	23-Sep-25	21-Sep-25 ■ 23-Sep-25																								
PETEC.PRO.1830	Đánh giá CBE	2d	24-Sep-25	25-Sep-25	24-Sep-25 ■ 25-Sep-25																								
PETEC.PRO.2010	Ngày ký hợp đồng	2d	26-Sep-25	27-Sep-25	26-Sep-25 ■ 27-Sep-25																								
PETEC.PRO.2060	Ngày giao hàng đến công trường	70d	28-Sep-25	06-Dec-25	28-Sep-25 ■ 06-Dec-25																								
THIẾT BỊ					25-Feb-26																								
Bơm ly tâm					25-Feb-26																								
PETEC.PRO.1390	Ban hành TRD	10d	15-Sep-25	24-Sep-25	15-Sep-25 ■ 24-Sep-25																								
PETEC.PRO.1890	Đánh giá TBE	10d	25-Sep-25	04-Oct-25	25-Sep-25 ■ 04-Oct-25																								

■ Critical Path
■ Actual Work
■ Remaining Work
■ Critical Remaining Work
◆ Milestone
— Summary

Page 3 of 12

(*) Thời gian thực hiện các công việc này không nằm trong thời gian thực hiện hợp đồng, nhưng không quá thời gian theo quy định.
 (**) Đây là ngày bàn giao mặt bằng dự kiến, cần cử vào ngày bàn giao thực tế của CĐT Nhà thầu sẽ cập nhật lại tiến độ và trình CĐT phê duyệt.

Date	Revision	Checked	Approved
04-May-25	Issue for Bidding	V.L.T	V.V.V
12-Aug-25	Issue for PO	V.L.T	V.V.V



DỰ ÁN MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG

Phụ lục 3 - Tiến Độ Thực Hiện



Activity ID	Activity Name	Original Duration	Start	Finish	2025												2026												2027
					Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan					
					Gantt chart visualization of activity durations and dependencies across months.																								
PETEC.PRO.2160	Đánh giá CBE	2d	05-Oct-25	06-Oct-25	05-Oct-25 06-Oct-25																								
PETEC.PRO.2220	Ngày ký hợp đồng	4d	07-Oct-25	10-Oct-25	07-Oct-25 10-Oct-25																								
PETEC.PRO.2290	Ngày giao hàng đến công trường	138d	11-Oct-25	25-Feb-26	11-Oct-25 25-Feb-26																								
Bơm bánh răng (cho FO)		164d	15-Sep-25	25-Feb-26	15-Sep-25 25-Feb-26																								
PETEC.PRO.1400	Ban hành TRD	10d	15-Sep-25	24-Sep-25	15-Sep-25 24-Sep-25																								
PETEC.PRO.1900	Đánh giá TBE	10d	25-Sep-25	04-Oct-25	25-Sep-25 04-Oct-25																								
PETEC.PRO.2170	Đánh giá CBE	2d	05-Oct-25	06-Oct-25	05-Oct-25 06-Oct-25																								
PETEC.PRO.2210	Ngày ký hợp đồng	4d	07-Oct-25	10-Oct-25	07-Oct-25 10-Oct-25																								
PETEC.PRO.2300	Ngày giao hàng đến công trường	138d	11-Oct-25	25-Feb-26	11-Oct-25 25-Feb-26																								
Bơm Phòng cháy chữa cháy		164d	15-Sep-25	25-Feb-26	15-Sep-25 25-Feb-26																								
PETEC.PRO.1410	Ban hành TRD	10d	15-Sep-25	24-Sep-25	15-Sep-25 24-Sep-25																								
PETEC.PRO.1910	Đánh giá TBE	10d	25-Sep-25	04-Oct-25	25-Sep-25 04-Oct-25																								
PETEC.PRO.2180	Đánh giá CBE	2d	05-Oct-25	06-Oct-25	05-Oct-25 06-Oct-25																								
PETEC.PRO.2230	Ngày ký hợp đồng	2d	07-Oct-25	08-Oct-25	07-Oct-25 08-Oct-25																								
PETEC.PRO.2250	Ngày giao hàng đến công trường	140d	09-Oct-25	25-Feb-26	09-Oct-25 25-Feb-26																								
Cần xuất bộ		118d	15-Sep-25	10-Jan-26	15-Sep-25 10-Jan-26																								
PETEC.PRO.1420	Ban hành TRD	7d	15-Sep-25	21-Sep-25	15-Sep-25 21-Sep-25																								
PETEC.PRO.1700	Đánh giá TBE	7d	22-Sep-25	28-Sep-25	22-Sep-25 28-Sep-25																								
PETEC.PRO.2080	Đánh giá CBE	2d	29-Sep-25	30-Sep-25	29-Sep-25 30-Sep-25																								
PETEC.PRO.2430	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 18-Oct-25																								
PETEC.PRO.2550	Ngày giao hàng đến công trường	84d	19-Oct-25	10-Jan-26	19-Oct-25 10-Jan-26																								
Thiết bị cơ khí trên bồn (Van xả khẩn cấp 24", Van thờ 12", Nắp ống thăm)		118d	15-Sep-25	10-Jan-26	15-Sep-25 10-Jan-26																								
PETEC.PRO.1430	Ban hành TRD	7d	15-Sep-25	21-Sep-25	15-Sep-25 21-Sep-25																								
PETEC.PRO.1710	Đánh giá TBE	7d	22-Sep-25	28-Sep-25	22-Sep-25 28-Sep-25																								
PETEC.PRO.2090	Đánh giá CBE	2d	29-Sep-25	30-Sep-25	29-Sep-25 30-Sep-25																								
PETEC.PRO.2540	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 18-Oct-25																								
PETEC.PRO.2660	Ngày giao hàng đến công trường	84d	19-Oct-25	10-Jan-26	19-Oct-25 10-Jan-26																								
DIỆN		122d	11-Sep-25	10-Jan-26	11-Sep-25 10-Jan-26																								
Tủ điện động lực		77d	11-Sep-25	26-Nov-25	11-Sep-25 26-Nov-25																								
PETEC.PRO.1230	Ban hành TRD	10d	11-Sep-25	20-Sep-25	11-Sep-25 20-Sep-25																								
PETEC.PRO.1640	Đánh giá TBE	7d	21-Sep-25	27-Sep-25	21-Sep-25 27-Sep-25																								
PETEC.PRO.2070	Đánh giá CBE	2d	28-Sep-25	29-Sep-25	28-Sep-25 29-Sep-25																								
PETEC.PRO.2100	Ngày ký hợp đồng	2d	30-Sep-25	01-Oct-25	30-Sep-25 01-Oct-25																								
PETEC.PRO.2110	Ngày giao hàng đến công trường	56d	02-Oct-25	26-Nov-25	02-Oct-25 26-Nov-25																								
Cáp điện động lực		94d	11-Sep-25	13-Dec-25	11-Sep-25 13-Dec-25																								
PETEC.PRO.1240	Ban hành TRD	7d	11-Sep-25	17-Sep-25	11-Sep-25 17-Sep-25																								
PETEC.PRO.1500	Đánh giá TBE	5d	18-Sep-25	22-Sep-25	18-Sep-25 22-Sep-25																								
PETEC.PRO.1780	Đánh giá CBE	2d	23-Sep-25	24-Sep-25	23-Sep-25 24-Sep-25																								
PETEC.PRO.2480	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 18-Oct-25																								
PETEC.PRO.2560	Ngày giao hàng đến công trường	56d	19-Oct-25	13-Dec-25	19-Oct-25 13-Dec-25																								
Hệ thống chống sét và tiếp địa		94d	11-Sep-25	13-Dec-25	11-Sep-25 13-Dec-25																								

■ Critical Path
■ Actual Work
■ Remaining Work
■ Critical Remaining Work
◆ Milestone
— Summary

Page 4 of 12

(*) Thời gian thực hiện các công việc này không nằm trong thời gian thực hiện hợp đồng, nhưng không quá thời gian theo quy định.
 (**) Đây là ngày bàn giao mặt bằng dự kiến, cần cử vào ngày bàn giao thực tế của CĐT Nhà thầu sẽ cập nhật lại tiến độ và trình CĐT phê duyệt.

Date	Revision	Checked	Approved
04-May-25	Issue for Bidding	V.L.T	V.V.V
12-Aug-25	Issue for PO	V.L.T	V.V.V



DỰ ÁN MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG

Phụ lục 3 - Tiến Độ Thực Hiện



Activity ID	Activity Name	Original Duration	Start	Finish	2025												2026												2027
					Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan					
Cáp cho hệ thống báo cháy					13-Dec-25																								
PETEC.PRO.1320	Ban hành TRD	7d	11-Sep-25	17-Sep-25	11-Sep-25 ■ 17-Sep-25																								
PETEC.PRO.1580	Đánh giá TBE	5d	18-Sep-25	22-Sep-25	18-Sep-25 ■ 22-Sep-25																								
PETEC.PRO.1810	Đánh giá CBE	2d	23-Sep-25	24-Sep-25	23-Sep-25 ■ 24-Sep-25																								
PETEC.PRO.2500	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 ■ 18-Oct-25																								
PETEC.PRO.2610	Ngày giao hàng đến công trường	56d	19-Oct-25	13-Dec-25	19-Oct-25 ■ 13-Dec-25																								
Hệ thống báo cháy (FA)					27-Dec-25																								
PETEC.PRO.1330	Ban hành TRD	7d	11-Sep-25	17-Sep-25	11-Sep-25 ■ 17-Sep-25																								
PETEC.PRO.1590	Đánh giá TBE	5d	18-Sep-25	22-Sep-25	18-Sep-25 ■ 22-Sep-25																								
PETEC.PRO.1820	Đánh giá CBE	2d	23-Sep-25	24-Sep-25	23-Sep-25 ■ 24-Sep-25																								
PETEC.PRO.2510	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 ■ 18-Oct-25																								
PETEC.PRO.2620	Ngày giao hàng đến công trường	70d	19-Oct-25	27-Dec-25	19-Oct-25 ■ 27-Dec-25																								
Máy phát điện Diesel					10-Jan-26																								
PETEC.PRO.1340	Ban hành TRD	7d	11-Sep-25	17-Sep-25	11-Sep-25 ■ 17-Sep-25																								
PETEC.PRO.1600	Đánh giá TBE	7d	18-Sep-25	24-Sep-25	18-Sep-25 ■ 24-Sep-25																								
PETEC.PRO.1920	Đánh giá CBE	2d	25-Sep-25	26-Sep-25	25-Sep-25 ■ 26-Sep-25																								
PETEC.PRO.2440	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 ■ 18-Oct-25																								
PETEC.PRO.2630	Ngày giao hàng đến công trường	84d	19-Oct-25	10-Jan-26	19-Oct-25 ■ 10-Jan-26																								
ĐIỀU KHIỂN					24-Jan-26																								
Cải hoán hệ thống giám sát DCS/SCADA					13-Dec-25																								
PETEC.PRO.1930	Ban hành TRD	10d	25-Sep-25	04-Oct-25	25-Sep-25 ■ 04-Oct-25																								
PETEC.PRO.2190	Đánh giá TBE	10d	05-Oct-25	14-Oct-25	05-Oct-25 ■ 14-Oct-25																								
PETEC.PRO.2370	Đánh giá CBE	2d	15-Oct-25	16-Oct-25	15-Oct-25 ■ 16-Oct-25																								
PETEC.PRO.2520	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 ■ 18-Oct-25																								
PETEC.PRO.2640	Ngày giao hàng đến công trường	56d	19-Oct-25	13-Dec-25	19-Oct-25 ■ 13-Dec-25																								
Thiết bị đo mức, bộ hiển thị, đo nhiệt độ bồn					24-Jan-26																								
PETEC.PRO.1940	Ban hành TRD	10d	25-Sep-25	04-Oct-25	25-Sep-25 ■ 04-Oct-25																								
PETEC.PRO.2200	Đánh giá TBE	10d	05-Oct-25	14-Oct-25	05-Oct-25 ■ 14-Oct-25																								
PETEC.PRO.2380	Đánh giá CBE	2d	15-Oct-25	16-Oct-25	15-Oct-25 ■ 16-Oct-25																								
PETEC.PRO.2530	Ngày ký hợp đồng	2d	17-Oct-25	18-Oct-25	17-Oct-25 ■ 18-Oct-25																								
PETEC.PRO.2650	Ngày giao hàng đến công trường	98d	19-Oct-25	24-Jan-26	19-Oct-25 ■ 24-Jan-26																								
Thiết bị đo lường					07-Jan-26																								
PETEC.PRO.1950	Ban hành TRD	7d	25-Sep-25	01-Oct-25	25-Sep-25 ■ 01-Oct-25																								
PETEC.PRO.2120	Đánh giá TBE	7d	02-Oct-25	08-Oct-25	02-Oct-25 ■ 08-Oct-25																								
PETEC.PRO.2260	Đánh giá CBE	2d	09-Oct-25	10-Oct-25	09-Oct-25 ■ 10-Oct-25																								
PETEC.PRO.2350	Ngày ký hợp đồng	2d	14-Oct-25	15-Oct-25	14-Oct-25 ■ 15-Oct-25																								
PETEC.PRO.2390	Ngày giao hàng đến công trường	84d	16-Oct-25	07-Jan-26	16-Oct-25 ■ 07-Jan-26																								
Cáp điều khiển					07-Jan-26																								
PETEC.PRO.1960	Ban hành TRD	7d	25-Sep-25	01-Oct-25	25-Sep-25 ■ 01-Oct-25																								
PETEC.PRO.2130	Đánh giá TBE	5d	02-Oct-25	06-Oct-25	02-Oct-25 ■ 06-Oct-25																								
PETEC.PRO.2240	Đánh giá CBE	2d	07-Oct-25	08-Oct-25	07-Oct-25 ■ 08-Oct-25																								

■ Critical Path
■ Actual Work
■ Remaining Work
■ Critical Remaining Work
◆ Milestone
▶ Summary

Page 6 of 12

(*) Thời gian thực hiện các công việc này không nằm trong thời gian thực hiện hợp đồng, nhưng không quá thời gian theo quy định.
 (**) Đây là ngày bản giao mặt bằng dự kiến, căn cứ vào ngày bản giao thực tế của CĐT Nhà thầu sẽ cập nhật lại tiến độ và trình CĐT phê duyệt.

Date	Revision	Checked	Approved
04-May-25	Issue for Bidding	V.L.T	V.V.V
12-Aug-25	Issue for PO	V.L.T	V.V.V



DỰ ÁN MỞ RỘNG SỨC CHỨA 40.000M3 KHO XĂNG DẦU PETEC HẢI PHÒNG

Phụ lục 3 - Tiến Độ Thực Hiện



Activity ID	Activity Name	Original Duration	Start	Finish	2025												2026												2027
					Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan					
					HẠNG MỤC ĐIỀU KHIỂN					▼ 26-Jun-26																			
PETEC.PRE1130	Loop test	5d	22-Jun-26	26-Jun-26	22-Jun-26 ■ 26-Jun-26																								
CHẠY THỬ VÀ BÀN GIAO					▶ 24-Jul-26																								
PETEC.COM1000	Chạy thử hệ thống PCC&CC	7d	29-May-26	04-Jun-26	29-May-26 ■ 04-Jun-26																								
PETEC.COM1010	Chạy thử hệ thống PCC&CC	25d	30-Jun-26	24-Jul-26	30-Jun-26 ■ 24-Jul-26																								
PETEC.COM1020	Kiểm tra đảm bảo hiệu suất	6d	19-Jul-26	24-Jul-26	19-Jul-26 ■ 24-Jul-26																								
PETEC.COM1030	Kiểm tra độ tin cậy	6d	19-Jul-26	24-Jul-26	19-Jul-26 ■ 24-Jul-26																								

- Critical Path
- Actual Work
- Remaining Work
- Critical Remaining Work
- ◆ Milestone
- ▶ Summary

(*) Thời gian thực hiện các công việc này không nằm trong thời gian thực hiện hợp đồng, nhưng không quá thời gian theo quy định.
 (**) Đây là ngày bàn giao mặt bằng dự kiến, căn cứ vào ngày bàn giao thực tế của CĐT Nhà thầu sẽ cập nhật lại tiến độ và trình CĐT phê duyệt.

Date	Revision	Checked	Approved
04-May-25	Issue for Bidding	V.L.T	V.V.V
12-Aug-25	Issue for PO	V.L.T	V.V.V